

Continuous high-temperature wall thickness monitoring of multiple refinery process units

In-service, high-temperature corrosion monitoring of equipment to maximise productivity, safety and plant availability.



Overview

An automated solution for in-service corrosion monitoring of multiple refinery process units, including Crude Distillation Unit (CDU), Fluid Catalytic Cracking Unit (FCCU), High Vacuum Distillation Unit (HVU) and Gas Processing Plant, was sought by a major oil company. The deployment was required to cover various process units spread over a 2 km² area and included wall thickness monitoring locations at process conditions of over 200 °C and as high as 520 °C.

- Enable operational decisions to be made and value to be generated from readily available real-time corrosion and asset integrity data that did not previously exist.
- Maintain the availability, up-time and profitability of ageing refining assets.
- Minimise the exposure of staff to hazardous locations during increased inspection frequencies.

The Challenge

The biggest challenge focussed around the extreme environment in which the monitoring system would be deployed:

- Sensors were required to operate continuously up to 380 °C under insulation to monitor corrosion and wall loss in pipes of various diameters, carrying various fluids and gas.
- Locations on the FCCU were required to operate at continuous operating temperatures up to 520°C.
- An intrinsically safe solution with Class 1 Div 1 / ATEX Zone 0 certification was required for the entire system
- The installation needed to be conducted while the plant was operational and running at high temperature.

The Solution

- HotSense™ sensors were chosen because of their wide operating temperature range: -55 °C to +550 °C and their intrinsically safe FM Class 1 Div 1 certification. The low profile HotSense™ sensor can be installed under insulation and weatherproofing to prevent water ingress, inhibiting Corrosion Under Insulation.
- The HotSense™ strap deployment system can be used to rapidly attach sensors at corrosion monitoring locations during normal operating conditions, providing robust and reliable measurements.

- The CALIPERAY WirelessHART enabled system was coupled with the HotSense™ sensors to provide a wireless automated wall thickness monitoring solution. The CALIPERAY is intrinsically safe to match the FM Class 1 Div 1 certification of the HotSense™ sensors.
- A full industry-standard WirelessHART network was also established to provide robust and reliable data collection across all process units. Combined with the system software, data was made available at all the required control centres and also exported directly to the client Plant Integrity Monitoring Systems.

Execution

- The full system solution was successfully deployed during live plant operation, comprising over HotSense™ 100 sensors across the multiple process units together with a full WirelessHART network system. System software has been installed and data was made available at all the required control centres feeding the client's Plant Integrity Monitoring Systems.

Key deliverables

- Frequent, consistent and high-quality wall thickness data collection now enables the customer to **maximise plant availability and avoid unplanned shutdowns – expected payback < 1 year**
- Process and Production engineers have access to integrity data at key locations allowing **optimisation of feedstock, corrosion inhibitor strategy and process parameters** to be made, allowing profitable decisions to be made based on measurable data
- Maintenance and Turnaround planners can make informed decisions on repair and replacement, **optimising maintenance project costs and planning**
- Continuous monitoring enables wall thickness data to be automatically collected twice per day from hazardous locations - avoiding the requirement for scaffolding, hot work permits and exposure of staff to high temperature and hazardous environments –**enhancing safety and personnel risk reduction measures and educing inspection costs.**
- Installation during a normal production run allowed benefits and savings to be realised immediately instead of waiting for a very busy refinery Turnaround period in the future



Using HotSense™ installed sensors with CALIPERAY monitoring nodes allowed for **automated, robust and reliable wall thickness measurements to be collected from live high temperature assets.**